

SUBCONTRACTOR FIELD WORK ORDER**Crew 2: Drywall, Framing & Insulation****INSURED / CLIENT**

David & Amanda Torres

SITE ADDRESS

Confirm with the superintendent before mobilization

CLAIM / CARRIER

CB-2026-8812 | Chubb Insurance | Policy CHU-77218-A

SCOPE REFERENCE

T-2, T-4, T-5

SITE RULES

Hours: Monday-Friday, 7:00 AM - 5:00 PM. Weekend work requires superintendent approval 24h in advance.

Parking / Staging: Park only in the approved staging area; keep driveways and streets clear for material deliveries.

Dust & Debris: Stage debris in the designated dumpster/containment area. No debris may remain in occupied areas overnight.

Emergency: Notify the on-site superintendent immediately for any incident; call 911 for gas, electrical or flooding emergencies.

Locate the main panel and water shutoff before starting.

\$ CONTRACT AMOUNT & BUDGET LINE LINKAGE

TASK	TRADE PACKAGE	AMOUNT
T-2	Framing & Structural <i>Sub bid</i>	\$5,200.00
T-4	Insulation <i>Sub bid</i>	\$1,850.00
T-5	Drywall & Wall Prep <i>Sub bid</i>	\$9,800.00
TOTAL CONTRACT AMOUNT		\$16,850.00

1 SCOPE SUMMARY

Perform insulation (batt, blown, vapor barrier), framing repairs, drywall hang, patch, tape, float and machine textures for: Framing & Structural, Insulation, Drywall & Wall Prep. Work only from the approved field scope; report any variance to the superintendent before proceeding.

2 SAFETY, SITE PROTECTION & CONTAINMENT

- Verify framing is structurally sound and moisture content is below 16% before enclosing.
- Maintain dust containment; use vacuums with HEPA filtration on all cutting tools.
- Wear eye protection and dust masks for cutting, sanding and texture spraying.
- Protect finished floors and adjacent surfaces before hanging or spraying.
- Scaffold or lift equipment must be stable and rated for the working height.

3 STEP-BY-STEP FIELD INSTRUCTIONS

Scope Execution

- Complete the Framing & Structural scope described in the approved estimate: Sister 8 burnt 2x6 ceiling joists, rebuild kitchen partition wall framing, install structural header over island span. (3 working day(s)).
- Complete the Insulation scope described in the approved estimate: Install R-30 mineral wool fire-resistant batt insulation in ceiling joist bays and R-15 batt in exterior wall cavities. (2 working day(s)).
- Complete the Drywall & Wall Prep scope described in the approved estimate: Hang 5/8" Type X fire-rated drywall on kitchen ceiling and walls, Level 4 finish with smooth skim coat ready for paint. (6 working day(s)).

Quantities & Material Staging

- Verify all field quantities against the approved scope before ordering or cutting materials.

Sequencing (CREW-2)

- T-2: mobilize only after predecessor scope (T-1) is complete and accepted.
- T-4: mobilize only after predecessor scope (T-3) is complete and accepted.
- T-5: mobilize only after predecessor scope (T-4) is complete and accepted.

4 MATERIAL SPECIFICATIONS & FASTENERS

- All materials must match the approved manufacturer specifications and be staged in a dry, protected area.
- Fasten per manufacturer requirements; use corrosion-resistant fasteners in wet or exterior areas.
- Verify quantities with the superintendent before installing; retain packaging and cut sheets for verification.

5 QUALITY CONTROL & PUNCHLIST STANDARDS

- [] Framing plumb, level and square; blocking installed where fixtures require support.
- [] Insulation fitted without gaps, voids or compression; vapor barrier sealed at seams.
- [] Joints taped, floated and sanded to Level 4 finish unless texture exceeds it.
- [] Texture uniform and blended into existing areas with no visible lap lines.
- [] Walk the work area with the superintendent and sign off on this sheet before demobilizing.

DO NOT PERFORM / SCOPE EXCLUSIONS

Do not perform any credited, omitted or out-of-scope work without a written change order.

SIGN-OFF & ACCEPTANCE

Crew Lead Signature

Print Name

Date

Subcontractor acknowledges the scope, quantities, materials and sequencing above. Any deviation requires a written change order approved by the superintendent before work continues.