

**SUBCONTRACTOR FIELD WORK ORDER****Crew 3: Flooring & Underlayment Installation****INSURED / CLIENT**

Michael &amp; Sarah Jenkins

**SITE ADDRESS**

Confirm with the superintendent before mobilization

**CLAIM / CARRIER**

92-8419-X21 | State Farm Insurance | Policy HO-9481028-2

**SCOPE REFERENCE**

T-7

**SITE RULES**

Hours: Monday-Friday, 7:00 AM - 5:00 PM. Weekend work requires superintendent approval 24h in advance.

Parking / Staging: Park only in the approved staging area; keep driveways and streets clear for material deliveries.

Dust &amp; Debris: Stage debris in the designated dumpster/containment area. No debris may remain in occupied areas overnight.

Emergency: Notify the on-site superintendent immediately for any incident; call 911 for gas, electrical or flooding emergencies.

Locate the main panel and water shutoff before starting.

**\$ CONTRACT AMOUNT & BUDGET LINE LINKAGE**

| TASK                         | TRADE PACKAGE              | AMOUNT            |
|------------------------------|----------------------------|-------------------|
| T-7                          | Flooring<br><i>Sub bid</i> | \$7,100.00        |
| <b>TOTAL CONTRACT AMOUNT</b> |                            | <b>\$7,100.00</b> |

**1 SCOPE SUMMARY**

Perform sound membrane/underlayment, click-lock lvp, laminate, sheet vinyl, tile, carpet/pad, t-molding and transitions for: Flooring. Work only from the approved field scope; report any variance to the superintendent before proceeding.

**2 SAFETY, SITE PROTECTION & CONTAINMENT**

- Test substrate moisture (under 5% wood / per manufacturer spec) and record readings before install.
- Acclimate flooring materials in the conditioned space per manufacturer requirements.
- Wear knee protection, gloves and cut-rated blades; keep blades fresh to avoid slips.
- Keep utility knives sheathed when not in use and sweep fasteners immediately.

**3 STEP-BY-STEP FIELD INSTRUCTIONS****Scope Execution**

- Complete the Flooring scope described in the approved estimate: Prep subfloor, install luxury vinyl plank (LVP) click-lock flooring in main living areas and 38oz nylon carpet in bedrooms. (3 working day(s)).

## Quantities & Material Staging

- Verify all field quantities against the approved scope before ordering or cutting materials.

## Sequencing (CREW-3)

- T-7: mobilize only after predecessor scope (T-5) is complete and accepted.

## 4 MATERIAL SPECIFICATIONS & FASTENERS

- All materials must match the approved manufacturer specifications and be staged in a dry, protected area.
- Fasten per manufacturer requirements; use corrosion-resistant fasteners in wet or exterior areas.
- Verify quantities with the superintendent before installing; retain packaging and cut sheets for verification.

## 5 QUALITY CONTROL & PUNCHLIST STANDARDS

- ☐ Substrate clean, flat and within manufacturer tolerance; no hollow spots or lippage.
- ☐ Expansion gaps maintained at all perimeter pinch points; transitions centered under door slabs.
- ☐ No peaking seams, telegraphing or pattern repetition where visible.
- ☐ Floor protected after install; homeowner walkthrough completed.
- ☐ Walk the work area with the superintendent and sign off on this sheet before demobilizing.

### DO NOT PERFORM / SCOPE EXCLUSIONS

Do not perform any credited, omitted or out-of-scope work without a written change order.

## SIGN-OFF & ACCEPTANCE

\_\_\_\_\_  
Crew Lead Signature

\_\_\_\_\_  
Print Name

\_\_\_\_\_  
Date

*Subcontractor acknowledges the scope, quantities, materials and sequencing above. Any deviation requires a written change order approved by the superintendent before work continues.*