

SUBCONTRACTOR FIELD WORK ORDER**Crew 8 (Supplemental): Roofing, Siding & Exterior Envelope****INSURED / CLIENT**

Robert Vance

SITE ADDRESS

Confirm with the superintendent before mobilization

CLAIM / CARRIER

LM-550912-01 | Liberty Mutual | Policy LMH-449102

SCOPE REFERENCE

T-2, T-3

SITE RULES

Hours: Monday-Friday, 7:00 AM - 5:00 PM. Weekend work requires superintendent approval 24h in advance.

Parking / Staging: Park only in the approved staging area; keep driveways and streets clear for material deliveries.

Dust & Debris: Stage debris in the designated dumpster/containment area. No debris may remain in occupied areas overnight.

Emergency: Notify the on-site superintendent immediately for any incident; call 911 for gas, electrical or flooding emergencies.

Locate the main panel and water shutoff before starting.

1 SCOPE SUMMARY

Perform roofing, gutters, siding, soffit and exterior glazing/windows where exterior scopes are included in the estimate for: Roofing & Exterior Decking, Siding, Gutters & Glazing. Work only from the approved field scope; report any variance to the superintendent before proceeding.

2 SAFETY, SITE PROTECTION & CONTAINMENT

- Fall protection required - harness, anchor point and ladder tie-off before roof access.
- Check weather window; no roofing work in wind above manufacturer limits or during precipitation.
- Stage materials so loads are balanced; never block egress or vented openings.

3 STEP-BY-STEP FIELD INSTRUCTIONS**Scope Execution**

- Complete the Roofing & Exterior Decking scope described in the approved estimate: Replace 6 sheets CDX roof decking, install synthetic underlayment, ice & water shield at eaves/valleys, 30-yr Owens Corning shingles. (3 working day(s)).
- Complete the Siding, Gutters & Glazing scope described in the approved estimate: Install Dutch lap vinyl siding on west gable, 6" seamless aluminum gutters, downspouts, replace 2 hail-shattered low-E sash units. (3 working day(s)).

Quantities & Material Staging

- Verify all field quantities against the approved scope before ordering or cutting materials.

Sequencing (CREW-8)

- T-2: mobilize only after predecessor scope (T-1) is complete and accepted.
- T-3: mobilize only after predecessor scope (T-2) is complete and accepted.

4 MATERIAL SPECIFICATIONS & FASTENERS

- All materials must match the approved manufacturer specifications and be staged in a dry, protected area.
- Fasten per manufacturer requirements; use corrosion-resistant fasteners in wet or exterior areas.
- Verify quantities with the superintendent before installing; retain packaging and cut sheets for verification.

5 QUALITY CONTROL & PUNCHLIST STANDARDS

- ☐ Decking/underlayment installed per code; flashing integrated at all penetrations.
- ☐ Roof penetrations and transitions water-tested before closing.
- ☐ Siding courses level, fastened to structure and sealed at openings.
- ☐ Walk the work area with the superintendent and sign off on this sheet before demobilizing.

DO NOT PERFORM / SCOPE EXCLUSIONS

Do not perform any credited, omitted or out-of-scope work without a written change order.

SIGN-OFF & ACCEPTANCE

Crew Lead Signature

Print Name

Date

Subcontractor acknowledges the scope, quantities, materials and sequencing above. Any deviation requires a written change order approved by the superintendent before work continues.