SUBCONTRACTOR FIELD WORK ORDER

Crew 2: Drywall, Framing & Insulation

INSURED / CLIENT
Robert Vance

SITE ADDRESS
Confirm with the superintendent before mobilization

CLAIM / CARRIER
LM-550912-01 | Liberty Mutual | Policy LMH-449102

SCOPE REFERENCE
T-4, T-5

SITE RULES

Hours: Monday-Friday, 7:00 AM - 5:00 PM. Weekend work requires superintendent approval 24h in advance.

Parking / Staging: Park only in the approved staging area; keep driveways and streets clear for material deliveries.

Dust & Debris: Stage debris in the designated dumpster/containment area. No debris may remain in occupied areas overnight.

Emergency: Notify the on-site superintendent immediately for any incident; call 911 for gas, electrical or flooding emergencies. Locate the main panel and water shutoff before starting.

$ CONTRACT AMOUNT & BUDGET LINE LINKAGE

TASK	TRADE PACKAGE	AMOUNT
T-4	Insulation *Sub bid*	**$1,720.00**
T-5	Drywall & Wall Prep *Sub bid*	**$5,640.00**
	TOTAL CONTRACT AMOUNT	**$7,360.00**

1 SCOPE SUMMARY

Perform insulation (batt, blown, vapor barrier), framing repairs, drywall hang, patch, tape, float and machine textures for: Insulation, Drywall & Wall Prep. Work only from the approved field scope; report any variance to the superintendent before proceeding.

2 SAFETY, SITE PROTECTION & CONTAINMENT

- Verify framing is structurally sound and moisture content is below 16% before enclosing.
- Maintain dust containment; use vacuums with HEPA filtration on all cutting tools.
- Wear eye protection and dust masks for cutting, sanding and texture spraying.
- Protect finished floors and adjacent surfaces before hanging or spraying.
- Scaffold or lift equipment must be stable and rated for the working height.

3 STEP-BY-STEP FIELD INSTRUCTIONS

Scope Execution

- Complete the Insulation scope described in the approved estimate: Blow-in cellulose insulation to attic cavity R-38 level over wet storm-collapsed insulation zones. (1 working day(s)).
- Complete the Drywall & Wall Prep scope described in the approved estimate: Replace 12 water-stained ceiling drywall sheets in master suite and dining room, tape, float, match knockdown texture. (4 working day(s)).

Quantities & Material Staging

- Verify all field quantities against the approved scope before ordering or cutting materials.

Sequencing (CREW-2)

- T-4: mobilize only after predecessor scope (T-2) is complete and accepted.
- T-5: mobilize only after predecessor scope (T-4) is complete and accepted.

4 MATERIAL SPECIFICATIONS & FASTENERS

- All materials must match the approved manufacturer specifications and be staged in a dry, protected area.
- Fasten per manufacturer requirements; use corrosion-resistant fasteners in wet or exterior areas.
- Verify quantities with the superintendent before installing; retain packaging and cut sheets for verification.

5 QUALITY CONTROL & PUNCHLIST STANDARDS

[ ] Framing plumb, level and square; blocking installed where fixtures require support.
[ ] Insulation fitted without gaps, voids or compression; vapor barrier sealed at seams.
[ ] Joints taped, floated and sanded to Level 4 finish unless texture exceeds it.
[ ] Texture uniform and blended into existing areas with no visible lap lines.
[ ] Walk the work area with the superintendent and sign off on this sheet before demobilizing.

DO NOT PERFORM / SCOPE EXCLUSIONS

Do not perform any credited, omitted or out-of-scope work without a written change order.

SIGN-OFF & ACCEPTANCE

Crew Lead Signature _____ Print Name _____ Date _____

Subcontractor acknowledges the scope, quantities, materials and sequencing above. Any deviation requires a written change order approved by the superintendent before work continues.