SUBCONTRACTOR FIELD WORK ORDER

# Crew 8 (Supplemental): Roofing, Siding & Exterior Envelope

INSURED / CLIENT
Robert Vance

SITE ADDRESS
Confirm with the superintendent before mobilization

CLAIM / CARRIER
LM-550912-01 | Liberty Mutual | Policy LMH-449102

SCOPE REFERENCE
T-2, T-3

**SITE RULES**

Hours: Monday-Friday, 7:00 AM - 5:00 PM. Weekend work requires superintendent approval 24h in advance.

Parking / Staging: Park only in the approved staging area; keep driveways and streets clear for material deliveries.

Dust & Debris: Stage debris in the designated dumpster/containment area. No debris may remain in occupied areas overnight.

Emergency: Notify the on-site superintendent immediately for any incident; call 911 for gas, electrical or flooding emergencies. Locate the main panel and water shutoff before starting.

## $ CONTRACT AMOUNT & BUDGET LINE LINKAGE

| TASK | TRADE PACKAGE | AMOUNT |
|---|---|---|
| **T-2** | Roofing & Exterior Decking<br>*Sub bid* | **$13,440.00** |
| **T-3** | Siding, Gutters & Glazing<br>*Sub bid* | **$8,520.00** |
| | **TOTAL CONTRACT AMOUNT** | **$21,960.00** |

## 1 SCOPE SUMMARY

Perform roofing, gutters, siding, soffit and exterior glazing/windows where exterior scopes are included in the estimate for: Roofing & Exterior Decking, Siding, Gutters & Glazing. Work only from the approved field scope; report any variance to the superintendent before proceeding.

## 2 SAFETY, SITE PROTECTION & CONTAINMENT

- Fall protection required - harness, anchor point and ladder tie-off before roof access.
- Check weather window; no roofing work in wind above manufacturer limits or during precipitation.
- Stage materials so loads are balanced; never block egress or vented openings.

## 3 STEP-BY-STEP FIELD INSTRUCTIONS

### Scope Execution

- Complete the Roofing & Exterior Decking scope described in the approved estimate: Replace 6 sheets CDX roof decking, install synthetic underlayment, ice & water shield at eaves/valleys, 30-yr Owens

Corning shingles. (3 working day(s)).
- Complete the Siding, Gutters & Glazing scope described in the approved estimate: Install Dutch lap vinyl siding on west gable, 6" seamless aluminum gutters, downspouts, replace 2 hail-shattered low-E sash units. (3 working day(s)).

### Quantities & Material Staging

- Verify all field quantities against the approved scope before ordering or cutting materials.

### Sequencing (CREW-8)

- T-2: mobilize only after predecessor scope (T-1) is complete and accepted.
- T-3: mobilize only after predecessor scope (T-2) is complete and accepted.

## 4 MATERIAL SPECIFICATIONS & FASTENERS

- All materials must match the approved manufacturer specifications and be staged in a dry, protected area.
- Fasten per manufacturer requirements; use corrosion-resistant fasteners in wet or exterior areas.
- Verify quantities with the superintendent before installing; retain packaging and cut sheets for verification.

## 5 QUALITY CONTROL & PUNCHLIST STANDARDS

[ ] Decking/underlayment installed per code; flashing integrated at all penetrations.
[ ] Roof penetrations and transitions water-tested before closing.
[ ] Siding courses level, fastened to structure and sealed at openings.
[ ] Walk the work area with the superintendent and sign off on this sheet before demobilizing.

**DO NOT PERFORM / SCOPE EXCLUSIONS**

Do not perform any credited, omitted or out-of-scope work without a written change order.

**SIGN-OFF & ACCEPTANCE**

Crew Lead Signature | Print Name | Date

*Subcontractor acknowledges the scope, quantities, materials and sequencing above. Any deviation requires a written change order approved by the superintendent before work continues.*